

LEVEL II

①

AD A109094

DELAWARE RIVER BASIN
BRANCH OF HOLBERT CREEK, WAYNE COUNTY

PENNSYLVANIA


BAYLY POND DAM

NDI ID NO. PA-00343

DER ID NO. 64-205

GEORGE W. BAYLY, ROBERT BAYLY &
ERNEST KANNENGEISSER

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM



DTIC
ELECTE
DEC 31 1981
E

Prepared by

Geo-Technical Services, Inc.

CONSULTING ENGINEERS & GEOLOGISTS

851 S. 19th Street

Harrisburg, Pennsylvania 17104

For

DEPARTMENT OF THE ARMY

Baltimore District, Corps of Engineers

Baltimore, Maryland 21203

Original contains color
plates: All DTIC reproduct-
ions will be in black and
white.

JULY 1981

This document has been approved
for public release and sale; its
distribution is unlimited.

81 12 28 189

DTIC FILE COPY

DELAWARE RIVER BASIN
BRANCH OF HOLBERT CREEK
PENNSYLVANIA

BAYLY POND DAM

NDI ID NO. PA-00343
DER ID NO. 64-205

GEORGE W. BAYLY, ROBERT BAYLY
AND ERNEST KANNENGEISSER

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM

Prepared by
GEO-Technical Services, Inc.
Consulting Engineers & Geologists
851 S. 19th Street
Harrisburg, Pennsylvania 17104

DACW31-81-C-0019

For
Department of the Army
Baltimore District, Corps of Engineers
Baltimore, Maryland 21203

July 1981

412434

| | |
|--------------------|--|
| Accession For | |
| NTIS GRA&I | <input checked="checked" type="checkbox"/> |
| DTIC TAB | <input type="checkbox"/> |
| Unannounced | <input type="checkbox"/> |
| Justification | |
| By | |
| Distribution/ | |
| Availability Codes | |
| Dist | Avail and/or Special |
| <i>A</i> | |

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the spillway design flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonable possible storm runoff), or fractions thereof. The spillway design flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

TABLE OF CONTENTS

| | <u>PAGE</u> |
|---|-------------|
| PREFACE | i |
| TABLE OF CONTENTS | ii |
| BRIEF ASSESSMENT OF GENERAL CONDITION AND RECOMMENDED ACTION | iii |
| OVERVIEW OF BAYLY POND DAM | v |
| | |
| SECTION 1 - GENERAL INFORMATION | 1 |
| SECTION 2 - ENGINEERING DATA | 4 |
| SECTION 3 - VISUAL INSPECTION | 5 |
| SECTION 4 - OPERATIONAL PROCEDURES | 7 |
| SECTION 5 - HYDROLOGY AND HYDRAULICS | 8 |
| SECTION 6 - EVALUATION OF STRUCTURAL STABILITY | 10 |
| SECTION 7 - ASSESSMENT AND RECOMMENDATIONS FOR REMEDIAL MEASURES | 11 |

APPENDICES

- APPENDIX A - VISUAL INSPECTION - CHECKLIST & EXHIBITS
- APPENDIX B - ENGINEERING DATA - CHECKLIST
- APPENDIX C - PHOTOGRAPHS
- APPENDIX D - HYDROLOGY AND HYDRAULICS
- APPENDIX E - EXHIBITS
- APPENDIX F - GEOLOGY

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM
BRIEF ASSESSMENT OF GENERAL CONDITION
AND
RECOMMENDED ACTION

Name of Dam: Bayly Pond Dam
NDI ID No. PA-00343
DER ID No. 64-205

Size: Small (11.7 feet high; 51 acre-feet)

Hazard Classification: Significant

Owner: George W. Bayly, Robert Bayly and
Ernest Kannengeisser
R.D. #4, Honesdale, Pa. 18431

State Located: Pennsylvania

County Located: Wayne

Stream: Branch of Holbert Creek

Date of Inspection: March 3, 1981

→ The Bayly Pond Dam is judged to be in good structural condition based on the visual inspection. Based on the location of the downstream dwellings and the fact that a few lives could be lost should the dam fail, the dam is classified as a significant hazard dam. Based on criteria established for these studies, the recommended Spillway Design Flood (SDF) varies between the 100-year flood and 1/2 of the Probable Maximum Flood (1/2 PMF). Because of the small reservoir storage capacity, the 100-year flood was selected for the SDF. Since the spillway cannot pass the 100-year flood without overtopping the dam, the spillway is rated as inadequate.

The following investigations and remedial measures are recommended for immediate implementation by the owner. All investigations and design of remedial measures should be performed under the direction of a Professional Engineer, experienced in the design and construction of dams.

- (1) Increase the spillway capacity to pass at least the 100-year flood flow without overtopping the dam and the dike.
- (2) Stabilize the upstream face of the dam against wave erosion.

BAYLY POND DAM

- (3) Verify the operational condition of the intake valve and provide other means to draw down the reservoir level in emergencies, should the valve be found inoperative.

In addition, the owner should institute the following operational and maintenance procedures.

- (1) Develop an emergency warning system which should include round-the-clock monitoring of the dam during periods of unusually heavy rains and plan to contact the few downstream residents who would be affected by a dam failure.
- (2) Institute an inspection program to include monitoring the existing depressions on the downstream slope of the dam and periodic operation of the outlet works to insure that a method of drawing down the pool is available and operable. As presently required by Bureau of Dams and Waterway Management of PENNDER, the program shall include an annual inspection of the dam by a Professional Engineer, experienced in the design and construction of dams. Deficiencies found during annual inspection should be remedied as necessary.

Submitted by:

GEO-TECHNICAL SERVICES, INC.



Gideon Yachin
GIDEON YACHIN, P.E.

Date: July 10, 1981

Approved by:

DEPARTMENT OF THE ARMY
BALTIMORE DISTRICT, CORPS OF ENGINEERS

James W. Peck
JAMES W. PECK, COLONEL
CORPS OF ENGINEERS
COMMANDER AND DISTRICT ENGINEER

Date: 3 Aug 81

BAYLY POND DAM (PA. - 00128)

(LEVEE IN BACKGROUND, ALONG ROAD)



OVERVIEW

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM
BAYLY POND DAM

NDI # PA-0343, PENNDA # 64-205

SECTION 1

GENERAL INFORMATION

1.1 General.

a. Authority: The inspection was performed pursuant to the authority granted by the National Dam Inspection Act, Public Law 92-367, to the Secretary of the Army, through the Corps of Engineers, to conduct inspections of dams throughout the United States.

b. Purpose: The purpose of this inspection is to determine if the dam constitutes a hazard to human life or property.

1.2 Description of Project.

a. Dam & Appurtenances: The Bayly Pond Dam is an earthfill structure terminating in earthen abutments. The dam has a maximum height of 11.7 feet and has a total length of 521 feet. The spillway is a 16 foot wide excavated earth channel in the left abutment. The outlet works is reported to consist of a small concrete intake box with a trash rack and manual slide gate. The intake box is connected to a 6-inch diameter steel pipe which has a gate valve located near the intake box. Flow through the 6-inch pipe is conveyed downstream through a 10-inch diameter steel pipe. A 12-inch steel riser pipe is also connected to the 10-inch outlet and serves to release low flow discharges from the reservoir.

There is an earthfill dike located approximately 120 feet south of the main dam. The dike is 250 feet in length and has a maximum height of 4.8 feet.

b. Location: The dam is situated on a branch of Holbert Creek in Berlin Township, Wayne County, Pennsylvania. The dam's location is approximately 1.5 miles east of Laurella, Pennsylvania, and is on the White Mills USGS 7.5 minute Quadrangle Map at Latitude 41°-36.0' and Longitude 75°-10.9'. A Location Map is shown in Exhibit E-1.

c. Size Classification: Small (11.7 feet high, 51 acre-feet).

d. Hazard Classification: Significant (see paragraph 3.1e).

e. Ownership: Mr. George W. Bayly, Robert Bayly and Ernest Kannengiesser, R. D. #4, Honesdale, Pennsylvania 18431.

f. Purpose of Dam: Recreation.

g. Design and Construction History: The dam was constructed in 1961 by Maynard Freeman, R. D. #4, Honesdale Pennsylvania. No design drawings, computations or "as-built" drawings are available.

h. Normal Operating Procedure: The 12-inch riser maintains the pool at low flow. The gate valve and slide gate are normally closed.

1.3 Pertinent Data.

| | |
|---|-----------|
| a. <u>Drainage Area</u> : | 0.12 mile |
| b. <u>Discharge at Dam Site (cfs)</u> : | |
| Maximum known flood at dam site | Unknown |
| Outlet conduit at maximum pool | 3 cfs |
| Total spillway capacity at maximum pool | 13 cfs |
| c. <u>Elevation (USGS Datum feet)</u> : See paragraph 3.1a for datum. | |
| Top of dam | 1396.5 |
| Top of dike | 1395.8 |
| Maximum Pool | 1395.8 |
| Normal Pool (see paragraph 3.1c (2)) | 1395.4 |
| Upstream invert outlet works | Unknown |
| Downstream invert outlet works | 1384.8 |
| Streambed at center line of dam | Unknown |
| Maximum Tailwater | Unknown |
| Downstream toe | 1384.8 |
| d. <u>Reservoir Length (feet)</u> | |
| Normal pool level | 900+ |
| Maximum pool level | 910+ |
| e. <u>Storage (acre-feet)</u> | |
| Normal pool level | 45 |
| Maximum pool level | 51 |
| f. <u>Reservoir Surface (acres)</u> | |
| Normal pool level | 13 |
| Maximum pool level | 17 |
| g. <u>Dam</u> | |
| Type | Earth |
| Length (dam) | 521 feet |
| Length (dike) | 250 feet |
| Height (dam) | 11.7 feet |
| Height (dike) | 4.8 feet |
| Top width (dam) | 10 feet |
| Top width (dike) | 9 feet |
| Side slopes: | |
| Dam Downstream; Varies from 2.7H:1V to 5H:1V | |
| Dam Upstream; Approximately 3H:1V | |
| Dike Downstream; Varies from 5H:1V to 12H:1V | |
| Dike Upstream; Approximately 3H:1V | |
| Zoning | None |
| Impervious core | None |
| Cutoff (reported by owner for both dam & dike) | |
| 3 to 5 feet deep, 8 feet wide trench. | |
| Grout Curtain | None |

h. Regulating Outlet

Type - A slide gate on intake box followed by a 6" diameter gate valve on a section of 6" diameter steel pipe. Both are submerged and discharge to a 10" diameter steel outlet pipe.

Length 60+ feet

Access - By diving from dam crest

i. Spillway (Emergency)

Type - Excavated earth - Trapezoidal

Length of crest 16 feet

Length of outlet channel 100+ feet

Crest Elevation 1395.4

Gates None

Upstream channel Earth

Downstream channel Earth

j. Spillway (Service), as reported by owner.

Type - 12" diameter steel riser pipe at the upstream end of a 10" diameter outlet pipe.

Crest Elevation (reported 12" below emergency spillway crest)

SECTION 2 ENGINEERING DATA

2.1 Design.

There is no available information relative to the design of the dam.

2.2 Construction Records.

The dam was constructed in 1961 by a local contractor, Mr. Maynard Freeman. A verbal description of the facilities was given by the owner.

2.3 Operation.

Non-documented.

2.4 Other Investigations.

No other documented investigations were available for use in evaluating the dam.

2.5 Evaluation.

a. Availability of Data: There are no plans or other information available on the design and construction of the dam.

b. Adequacy: In the absence of design plans, specifications, or construction records, assessment of the dam and its safety must be based on the visual inspection and the Hydrologic and Hydraulic analysis presented in Section 5.

SECTION 3 VISUAL INSPECTION

3.1 Observations.

a. General: The overall appearance of the dam and appurtenant dike is good. A plan of the dam and annotated field observations are shown on Exhibit A-1, Appendix A. Surveyed profiles and typical dam and dike sections are presented in Exhibits A-2, A-3 and A-4. The survey datum for this inspection is based on interpolation of the USGS Contour Lines (see Exhibit E-1). On the inspection date (3/3/1981), the pool was at elevation 1395.5, approximately 0.1 foot above the spillway crest. Pertinent observed features are indicated on the photographs in Appendix C.

b. Embankments: The earth embankments of the dam and dike appear generally sound. The upper 3' of the embankment on the pond side has been eroded by wave action. Softening of the embankment by cattle coming to drink water has aggravated this situation. No seepage areas were observed at the toe of the slopes or at the junction of the abutment and embankment. Marshy areas exist below the toe of both the dam and dike. According to the dam owner, the marshy areas existed prior to the dam's construction. Four shallow drainage ditches have been dug to drain the marshy area. Two 3-foot diameter shallow surface depressions are located on the downstream face of the dam, 70 feet right of the outlet pipe. Although there was no evidence of internal erosion or "piping" downstream of these depressions, they should be monitored (see paragraphs 6.1a and 7.2b). A 5-foot length of the dike crest near the center of the embankment has been backfilled with stone and earth, indicating overtopping erosion in this area.

c. Appurtenant Structures:

(1) Spillway: The appearance of the earth spillway is good. Only minor erosion was evident in the spillway channel (see Photograph 1).

(2) Outlet Works: The outlet end of the 10-inch diameter steel pipe appears to be in good condition. A sketch based on the following description is presented in Exhibit A-5. The outlet works was described by the owner as having a small concrete intake box connected to a 10-inch diameter outlet pipe by a short length of 6-inch diameter pipe that has a 6-inch gate valve. A 12-inch steel riser pipe is also connected to the 10-inch outlet. The top of the riser, described as being approximately 12 inches below the emergency spillway crest, was not visible on the day of the inspection. The outlet pipe discharge observed during the inspection was a fraction of the flow expected for the outlet works with a 1-foot head over the crest of the riser pipe (see Exhibit A-5). Consequently, the outlet works is considered to be partially blocked and the elevation of the emergency spillway crest is the normal pool elevation.

d. Reservoir Area: The watershed draining to the pond is farm land and woodland with 5 to 20 percent slopes. There is no evidence of unstable slopes which would affect the dam stability. The watershed features are presented in Exhibit E-1. Geologic conditions of the general area are described in Appendix F. The potential of increased development changing the hydrologic characteristics of the watershed is considered to be remote.

e. Downstream Channel: The channel immediately downstream of the dam is a flat natural marshy area. The first potential damage area is a road culvert, located 600 feet downstream of the dam. About 650 feet downstream are two residential structures located within 50 feet of the stream and 1.5 to 5.0 feet above it (see Photograph 5, Appendix C). Downstream of the dike, there is no road culvert to accommodate frequent overtopping of the dike without flooding the road.

A 15-foot high SCS flood control dam is located 4200 feet downstream of Bayly Pond. This dam is Quarno Dam, NDI ID No. PA-00089, and has been inspected and is classified as a High Hazard Structure. The dam is described in the 1981 inspection report prepared by Berger Associates (see also paragraph 5.3d).

Based on the location of the downstream dwellings and the fact that a few lives could be lost should the dam fail, the dam is classified as a significant hazard structure.

SECTION 4
OPERATIONAL PROCEDURES

4.1 Normal Operating Procedures.

The reservoir is maintained at normal pool by excess flow being discharged through the riser and over the earth spillway.

4.2 Maintenance of Dam.

Maintenance of the dam consists of mowing the grass slopes and repairing minor erosion channels.

4.3 Maintenance of Operating Facilities.

The outlet facilities are not systematically operated. At the time of inspection, their functional status could not be determined. The owner has periodically released water for livestock during dry periods.

4.4 Warning System.

There is no formal warning system in effect at the present time.

4.5 Evaluation.

The maintenance of the dam, dike and spillway is good. The frequency of inspections of the outlet works operating facilities should be increased.

SECTION 5 HYDROLOGY AND HYDRAULICS

5.1 Design Data.

There are no hydrologic or hydraulic data available for Bayly Pond Dam.

5.2 Experience Data.

There are no records available relative to maximum stages or discharges at the dam. The visual inspection suggests that the dike has been overtopped at least on one occasion (see Paragraph 3.1b).

5.3 Visual Observations.

Based on the visual inspection and field survey described in Section 3, the observations relevant to hydrology and hydraulics are evaluated as follows:

a. Embankments: The spillway elevation is 1395.4 and the low point on the dike is 1395.8, resulting in only 0.4 feet of free-board. The variation in dam and dike crest elevation is shown in Appendix D and is based on the field survey on the inspection date.

The downstream channel is wide and the total overtopping length at high discharges is 771 feet (for the dam and dike combined). Therefore, backwater would have no effect on the overtopping analysis.

b. Spillway: The spillway is a trapezoidal earth channel, 16 feet wide at the bottom, consisting of a short approach channel and followed by an earth outlet channel, having a bottom slope of 0.8% and terminating approximately 100 feet downstream of the left abutment of the dam. The spillway flow is spread over the natural ground surface having an 8% slope, prior to discharging into the stream channel. Normal depth flow conditions control the discharges at low stages in the channel. At higher stages, the flow over the spillway crest is at critical depth. A rating curve for the spillway is presented in Appendix D. The spillway is shown in Photographs 1 and 2, Appendix C.

c. Reservoir Area: There are no upstream hydraulic structures which would influence flood flow into Bayly Pond.

Future development to the extent that would alter hydrologic and hydraulic conditions is not anticipated.

d. Downstream Conditions: There are no downstream conditions which would affect Bayly Pond Dam hydraulically.

As mentioned in Section 3, the Quarno Dam, a high hazard structure, is located 4200 feet downstream of Bayly Pond Dam. According to its National Dam Inspection Phase I Report, the Quarno Dam has adequate spillway capacity and storage to be able to pass the full PMF without overtopping.

It is judged that a breach of Bayly Pond Dam would have no adverse effect on the stability of the Quarno Dam. Supporting computations are presented in Appendix D.

5.4 Method of Analysis.

Hydrologic and hydraulic evaluation was made in accordance with the procedures and guidelines established by the U.S. Army Corps of Engineers, Baltimore District, Phase I Safety Inspection of Dams. The analysis is presented in Appendix D.

5.5 Summary of Analysis.

a. Spillway Design Flood (SDF): According to criteria established by the office of the Chief of Engineers (OCE), the Spillway Design Flood (SDF) for the size (small) and hazard potential (significant) of the Bayly Pond Dam is between the 100-year flood and the one-half Probable Maximum Flood (1/2 PMF). The top of the dike is lower than the crest of the dam and the discharge over the dike bypasses the hazard area immediately downstream of the dam. Because of the small reservoir storage capacity and because failure of the dike may precede the failure of the dam, the 100-year flood is selected as the SDF for the Bayly Pond Dam.

b. Results of Analysis: Pertinent results are presented in Appendix D. The analysis reveals that under the prevailing top of dam and dike elevations, the combined discharge of service spillway and the emergency spillway is 13 CFS (cubic feet per second), when the water surface in Bayly Pond reaches the low point on the crest of the dike. The computed 100-year flood for the 0.12 square-mile drainage area above the dam is 130 cfs. Consequently, the present total capacity of the spillway is approximately 10 percent of the SDF. Should the crest of the dam and dike be brought to elevation 1397.2, or 1.4 feet above the low point on top of the dike, the spillway capacity will increase from the present 13 cfs to 130 cfs. Although outflow of water from Bayly Pond resulting from dike failure would bypass the hazard area downstream of the dam, frequent overtopping of the dike would overtop the road immediately downstream of the dike.

5.6 Spillway Adequacy.

Because the present capacity of the spillway will not pass the selected SDF without overtopping the dike and the dam, the spillway is rated as inadequate.

SECTION 6 EVALUATION OF STRUCTURAL STABILITY

6.1 Visual Observations.

The visual inspection of Bayly Pond Dam is described in Section 3. Observations relevant to the dam's structural stability are evaluated below:

a. Dam: Two 3-foot diameter saucer shaped depressions exist on the downstream slope of the dam (see paragraph 3.1b). The cause of these depressions cannot be evaluated from the available information. There is no evidence of piping to suggest internal erosion of the embankment.

b. Appurtenant Structures:

(1) Spillway: The spillway appears to be sound with no significant erosion in the outlet channel or on the steep bank at the termination of the excavated channel.

(2) Outlet Works: On the day of the inspection, the outlet pipe was not flowing full (see Photograph 3, Appendix C). Since the intake was submerged and the valve was inaccessible, pressure flow in the conduit could not be attained. Observations during pressure flow conditions are essential for the evaluation of structural stability.

6.2 Design and Construction Data.

There is no documented design or construction data.

6.3 Past Performance.

Except for the apparent overtopping of the dike, the dam has performed adequately since its construction in 1961.

6.4 Stability.

a. Static: The dam is considered to be stable under static loading conditions.

b. Seismic: The dam is located in seismic zone 1. If the dam has adequate structural stability under static conditions, it is assumed to be able to withstand the minor seismic forces expected in this zone.

SECTION 7
ASSESSMENT AND RECOMMENDATIONS FOR REMEDIAL MEASURES

7.1 Dam Assessment.

a. Safety:

(1) The Bayly Pond Dam is judged to be in good structural condition based on the visual inspection. Based on the location of the downstream dwellings and the fact that a few lives could be lost should the dam fail, the dam is classified as a significant hazard dam. Based on criteria established for these studies, the recommended Spillway Design Flood (SDF) varies between the 100-year flood and 1/2 of the Probable Maximum Flood (1/2 PMF). Because of the small reservoir storage capacity, the 100-year flood was selected for the SDF. Since the spillway cannot pass the 100-year flood without overtopping the dam, the spillway is rated as inadequate.

(2) A summary of the observed deficiencies is described below:

| <u>DESCRIPTION</u> | <u>OBSERVED DEFICIENCIES</u> |
|-------------------------------|---|
| <u>Earth Embankments</u> | |
| Dam | Erosion of the upstream face of the dam due to wave action. |
| Dike | The low point on the crest of the dike is 0.4 foot above the crest of the emergency spillway. Frequent overtopping of the dike is expected. |
| <u>Appurtenant Structures</u> | |
| Spillway | Inadequate capacity to discharge the SDF without overtopping the dike and the dam. |
| Outlet Works | The operational condition of the inlet valve requires verification. Means to draw down the reservoir must be provided in emergencies. |

b. Adequacy of Information: There are no design or construction data available for Bayly Pond Dam. The visual inspection and computations performed as part of this study, as well as the past performance of the facility, are sufficient for the Phase I Dam Safety assessment, delineated in sub-paragraph a., aforementioned.

c. Urgency: The recommendations presented in Section 7.2 should be implemented immediately.

d. Necessity for Further Investigations: In order to accomplish some of the remedial measures outlined in paragraph 7.2, further investigation by a Professional Engineer experienced in the design and construction of dams will be necessary.

7.2 Recommendations and Remedial Measures.

a. The following investigations and remedial measures are recommended for immediate implementation by the owner.

(1) Increase the spillway capacity to pass at least the 100-year flood flow without overtopping the dam and the dike.

(2) Stabilize the upstream face of the dam against wave erosion.

(3) Verify the operational condition of the intake valve and provide other means to draw down the reservoir level in emergencies, should the valve be found inoperative.


b. In addition, the owner should institute the following operational and maintenance procedures:

(1) Develop an emergency warning system which should include round-the-clock monitoring of the dam during periods of unusually heavy rains and a plan to contact the few downstream residents who would be affected by a dam failure.

(2) Institute an inspection program to include monitoring the existing depressions on the downstream slope of the dam and periodic operation of the outlet works to insure that a method of drawing down the pool is available and operable. As presently required by Bureau of Dams and Waterway Management of PENNDEP, the program shall include an annual inspection of the dam by a Professional Engineer, experienced in the design and construction of dams. Deficiencies found during annual inspection should be remedied as necessary.

APPENDIX A


VISUAL INSPECTION - CHECKLIST AND FIELD SKETCHES



BAYLY POND DAM **GENERAL PLAN - FIELD INSPECTION NOTES**

GEO-TECHNICAL SERVICES
Consulting Engineers & Geologists

SHEET NO. _____ OF _____
CALCULATED BY gfm DATE 4/3/1
CHECKED BY _____ DATE _____
DAM PROFILE



FOR PLAN 101

SHEET NO 1 OF 1

CALCULATED BY PJM DATE 6-11-81

CHECKED BY _____ DATE _____

SCALE HORIZ 1" = 50' VERT 1" = 1'






EXHIBIT A-6




SECTION A




SPILLWAY SECTION

TYPICAL DAM SECTIONS



SECTION B



OUTLET WORKS

TYPICAL DAM SECTIONS

CHECK LIST VISUAL INSPECTION PHASE 1

NAME OF DAM Bayly Pond Dam STATE Pennsylvania COUNTY Wayne

NDI # PA - 0343 PENNIDER # 64-0205

TYPE OF DAM Earthfill SIZE Small HAZARD CATEGORY Significant

DATE(S) INSPECTION March 3, 1981 WEATHER Partly Cloudy TEMPERATURE 20° F @ 9:00 a.m.

POOL ELEVATION AT TIME OF INSPECTION 1395.4 M.S.L.

TAIL WATER AT TIME OF INSPECTION 1384.8 M.S.L.

| INSPECTION PERSONNEL | OWNER REPRESENTATIVES | OTHERS |
|----------------------------|-------------------------|--------------------------|
| <u>G. Yachin, Engineer</u> | <u>G. W. Bayly</u> | <u>J. Chernesky, DER</u> |
| <u>J. Daiz, Geologist</u> | <u>E. Kannengiesser</u> | |
| <u>R. Mather, Surveyor</u> | | |
| | | |
| | | |

RECORDED BY J. Diaz

EMBANKMENT

| ITEM | OBSERVATIONS/REMARKS/RECOMMENDATIONS | NDIN PA - 0343 |
|--|--|----------------|
| SURFACE CRACKS | None | |
| UNUSUAL MOVEMENT OR CRACKING AT OR BEYOND THE TOE | None | |
| SLOUGHING OR EROSION OF EMBANKMENT AND ABUTMENT SLOPES | There are 6" to 12" high erosion scarps on the top 3' of the upstream slope due to wave action and cattle drinking water. There are two shallow depressions (3' dia. x 6" deep) on the downstream slope right of the outlet pipe. A 6" to 12" wide erosion ditch and low area on the dike is the result of past overtopping. This area has been backfilled with earth and cobbles. (see Exhibit A-1) | |
| VERTICAL AND HORIZONTAL ALIGNMENT OF THE CREST | Both Good. | |
| RIPRAP FAILURES | No Riprap. | |
| JUNCTION OF EMBANKMENT AND ABUTMENT, SPILLWAY AND DAM | Good. No visible seeps. A 30-foot wide area on the right end of the dam is about 0.6' lower than the average dam crest. The abutment then rises on a 20% slope. The left abutment has an emergency earth spillway (see Exhibit A-2). | |

EMBANKMENT

| ITEM | OBSERVATIONS/REMARKS/RECOMMENDATIONS | NDI# PA - 0343 |
|--|--|----------------|
| DAMP AREAS IRREGULAR VEGETA- TION (LUSH OR DEAD PLANTS) | Four shallow drainage ditches extend downstream from toe of the main dam in order to drain a pre-existing marshy area. The marshy area downstream of dike also existed prior to dike construction. | |
| ANY NOTICEABLE SEEPAGE | None | |
| STAFF GAGE AND RECORDER | None | |
| DRAINS | None | |
| ROCK OUTCROPS | None | |
| CUT-OFF | A cut-off trench (3 to 5 feet deep X 8 feet wide) was excavated and backfilled with impervious material along the dam and dike centerlines (Description by owner). | |

OUTLET WORKS

| ITEM | OBSERVATIONS/REMARKS/RECOMMENDATIONS | NDI# PA 0343 |
|--|---|--------------|
| INTAKE STRUCTURE | A concrete intake box with trash rack and manual slide gate is connected to a 6" steel outlet pipe with a 6" gate valve. The 6" pipe discharges into a 10" diameter steel outlet pipe (description by owner). | |
| OUTLET CONDUIT (CRACKING AND SPALLING OF CON- CRETE SURFACES) | 10" diameter steel pipe. | |
| OUTLET STRUCTURE | None | |
| OUTLET CHANNEL | The outlet channel is an earth channel that connects to one of the marsh drainage ditches (see Exhibit A-1). | |
| GATE(S) AND OPER- ATIONAL EQUIPMENT | A manual slide gate on concrete intake box followed by a 6" gate valve. Both require under water operation (description by owner). | |
| | | |

EMERGENCY SPILLWAY

| ITEM | OBSERVATIONS/REMARKS/RECOMMENDATIONS | NDIS PA - 0343 |
|----------------------------------|---|----------------|
| TYPE AND CONDITION | Earth channel (16' wide x 1.7+ feet deep). There is a minor erosion ditch (3" deep, 6" wide) in the center of the spillway channel. | |
| APPROACH CHANNEL | Short earth channel on left abutment. | |
| SPILLWAY CHANNEL AND SIDEWALLS | Earth slopes. | |
| STILLING BASIN PLUNGE POOL | None. Outlet channel discharges directly on left abutment slope. | |
| DISCHARGE CHANNEL | The spillway discharge channel widens to 25 feet, curves toward the center of the valley and discharges onto the natural left abutment slope. | |
| BRIDGE AND PIERS EMERGENCY GATES | None | |

SERVICE SPILLWAY

| ITEM | OBSERVATIONS/REMARKS/RECOMMENDATIONS | NDW PA- 0343 |
|--------------------|--|--------------|
| TYPE AND CONDITION | A 12" diameter steel riser pipe at the upstream end of the 10" diameter outlet pipe (owner's description). The top of the riser was submerged (owner reports top as about 1' below water surface). | |
| APPROACH CHANNEL | N.A. | |
| OUTLET STRUCTURE | None | |
| DISCHARGE CHANNEL | An earth channel discharging into one of the marsh area drainage ditches. | |
| | | |
| | | |

INSTRUMENTATION

| ITEM | OBSERVATIONS/REMARKS/RECOMMENDATIONS | NDIN PA - 0343 |
|-----------------------|--------------------------------------|----------------|
| MONUMENTATION SURVEYS | None | |
| OBSERVATION WELLS | None | |
| WEIRS | None | |
| PIEZOMETERS | None | |
| OTHERS | None | |
| | | |

RESERVOIR AREA AND DOWNSTREAM CHANNEL

| ITEM | OBSERVATIONS/REMARKS/RECOMMENDATIONS | NDIN PA - 0343 |
|--|--|----------------|
| SLOPES: RESERVOIR | The right abutment is a grass slope of 15 to 20 percent. The left abutment is a grass slope of 10 to 20 percent. The upstream wooded slopes are 20%+. There are no unstable slope conditions that would affect the stability of the dam. | |
| SEDIMENTATION | None | |
| DOWNSTREAM CHANNEL (OBSTRUCTIONS, DEBRIS, ETC.) | None. The downstream grass meadow area has 4 shallow drainage ditches parallel to the stream valley. About 550' downstream is a 6' diameter RCP road culvert. About 4200' downstream is a flood control dam (SCS). | |
| SLOPES: CHANNEL VALLEY | Between the Township road and the downstream flood control dam, the channel valley is a wide, flat wooded natural marsh area. | |
| APPROXIMATE NUMBER OF HOMES AND POPULATION | 2 homes, 650 feet downstream of dam and 3 trailers downstream of the SCS flood control dam (Quarno Dam, located 4200' downstream of Bayly Pond Dam). | |
| | | |

APPENDIX B

ENGINEERING DATA - CHECKLIST

**CHECK LIST
ENGINEERING DATA
PHASE I**

NAME OF DAM Bayly Pond Dam

| ITEM | REMARKS | NDIN PA - 0343 |
|---|---|----------------|
| PERSONS INTERVIEWED AND TITLE | G. W. Bayley, Owner | |
| REGIONAL VICINITY MAP | See Exhibit E-1, Appendix E. | |
| CONSTRUCTION HISTORY | Owner reports dam was constructed in 1961 by Maynard Freeman, R. D. #4, Honesdale, Pennsylvania. There are no records available. | |
| AVAILABLE DRAWINGS | There are no design or construction plans available. The owner described some of the facilities that are now under water or buried. | |
| TYPICAL DAM SECTIONS | See Exhibits A-1 thru A-5, Appendix A. | |
| OUTLETS PLAN DETAILS DISCHARGE RATINGS | Not available. Not available. | |

**CHECK LIST
ENGINEERING DATA
PHASE I
(CONTINUED)**

| ITEM | REMARKS | NDI# PA - 0343 |
|---|--|----------------|
| SPILLWAY PLAN SECTION DETAILS | None available. A general plan and typical sections (from survey on inspection date) are shown on Exhibits A-1 thru A-5, Appendix A. | |
| OPERATING EQUIP- MENT PLANS AND DETAILS | None available. | |
| DESIGN REPORTS | None available. | |
| GEOLOGY REPORTS | None available. | |
| DESIGN COMPUTATIONS: HYDROLOGY AND HYDRAULICS STABILITY ANALYSES SEEPAGE ANALYSES | None available. | |
| MATERIAL INVESTIGATIONS: BORING RECORDS LABORATORY TESTING FIELD TESTING | None available. | |

**CHECK LIST
ENGINEERING DATA
PHASE I
(CONTINUED)**

| ITEM | REMARKS | NDH# PA. 0343 |
|--|--|---------------|
| BORROW SOURCES | No information available. | |
| POST CONSTRUCTION DAM SURVEYS | None available other than the survey made for the present inspection on March 3, 1981. | |
| POST CONSTRUCTION ENGINEERING STUDIES AND REPORTS | None available. | |
| HIGH POOL RECORDS | None available. | |
| MONITORING SYSTEMS | None | |
| MODIFICATIONS | No information available. | |

**CHECK LIST
ENGINEERING DATA
PHASE I
(CONTINUED)**

| ITEM | REMARKS | NDIA PA - 0343 |
|---|------------------|----------------|
| PRIOR ACCIDENTS OR FAILURES | None reported. | |
| MAINTENANCE RECORDS MANUAL | None available. | |
| OPERATION RECORDS MANUAL | None available. | |
| OPERATIONAL PROCEDURES | Self-regulating. | |
| WARNING SYSTEM AND/OR COMMUNICATION FACILITIES | None. | |
| MISCELLANEOUS | | |

**CHECK LIST
HYDROLOGIC AND HYDRAULIC
ENGINEERING DATA**

NDI ID # PA-0343
PENNER ID # 64-205

SIZE OF DRAINAGE AREA: 0.12 square mile
ELEVATION TOP NORMAL POOL 1395.4 STORAGE CAPACITY 45-acre feet
ELEVATION TOP FLOOD CONTROL POOL 1395.8 STORAGE CAPACITY 51 acre-feet
ELEVATION MAXIMUM DESIGN POOL No data STORAGE CAPACITY No data
DIKE
ELEVATION TOP ~~XXXX~~ 1395.8 STORAGE CAPACITY: 51 acre-feet

SPILLWAY DATA (Emergency Spillway)

CREST ELEVATION: 1395.4 (feet above m.s.l.)
TYPE: Trapezoidal excavated earth
CREST LENGTH: 16 feet
CHANNEL LENGTH: 100+ feet
SPILLOVER LOCATION: Left abutment
NUMBER AND TYPE OF GATES: None

OUTLET WORKS

TYPE: Concrete box with manual slide gate, 6" gate valve and 10" steel outlet pipe.
LOCATION: Center of dam
ENTRANCE INVERTS: Unknown (under water)
EXIT INVERTS: 1384.8 (feet above m.s.l.)
EMERGENCY DRAWDOWN FACILITIES Manual slide gate and 6" gate valve.


HYDROMETEOROLOGICAL GAGES

TYPE: None
LOCATION: N.A.
RECORDS: N.A.


MAXIMUM NON-DAMAGING DISCHARGE: 13 cfs

APPENDIX C

PHOTOGRAPHS



**BAYLY POND DAM
PHOTOGRAPHS LOCATION MAP**



**BAYLY POND DAM
DOWNSTREAM PHOTOGRAPHS LOCATION MAP**



1. VIEW OF DAM FACING RIGHT ABUTMENT, SPILLWAY IN FOREGROUND



2. UPSTREAM VIEW OF SPILLWAY. EXCAVATED CHANNEL ENDS AT ARROW



3. 10' DIA. OUTLET WORKS



4. VIEW OF DIKE FACING RIGHT ABUTMENT
BROWN AREA ON LEFT IS MARSH AREA



5. VIEW SHOWING DAM , MARSH AREA DRAINAGE DITCHES AND HOMES DOWNSTREAM



6. UPSTREAM VIEW OF ROAD CULVERT BELOW DAM



7. VIEW OF DOWNSTREAM FLOOD CONTROL DAM
(QUARNO DAM) FACING RIGHT ABUTMENT


APPENDIX D

HYDROLOGY AND HYDRAULICS

WHITE MILLS, PA.

N4130—W7507.5/7 5

1967
PHOTO REVISION 1973



GENERAL DATA

| | |
|--------------|------------------------|
| RIVER BASIN | DELAWARE |
| STREAM NAME | BRANCH OF HOLBERT CR'K |
| NDI - ID NO. | PA-0129 |
| DER - ID NO. | 64-205 |
| OWNER | GEO. W. BAYLY |
| LOCATION | BERLIN TWP. |
| COUNTY | WAYNE |
| LAT. | 41° 36.0' |
| LONG. | 75° 11.0' |
| SIZE | SMALL |
| HAZARD | |
| UPSTR. DAMS | NONE |
| DWNSTR. DAMS | QUARNO DAM PA-0089 |

RAINFALL DATA : (REF: HYDROMETEOROLOGICAL REPORT No. 33)

DELAWARE RIVER BASIN - ZONE I

PMP = 21.3" / 24HR

ADJUSTMENTS FOR DRAINAGE AREA < 10 mi²

| DURATION (HRS) | ADJUSTMENT (%) |
|-------------------|-------------------|
| 6 | 111 |
| 12 | 123 |
| 24 | 133 |
| 48 | 142 |

HYDROGRAPH DATA

DRAINAGE AREA = 0.12 mi² ZONE 1

SNYDER UNIT HYDROGRAPH COEFF. (as per CORAS)

$$C_p = 0.45$$

$$C_t = 1.23$$

LAG TIME (centroid within pond area)

$$T_p = C_t L'^{0.6} \quad (\text{as per COE})$$

L' = FROM RESERVOIR INLET TO DRAINAGE DIVIDE

$$L' = 1100'$$

$$T_p = 1.23 \left(\frac{1100}{5280} \right)^{0.6} = 0.48 \text{ Hr.}$$

DAM DATA


{ DAM HAS AN ADJACENT DIKE }

TOP DAM (LOW PT.) = 1396.5 (ON DAM)
DAM LENGTH (incl. spillway) = 521' (ON DIKE)
DAM HEIGHT (max.) = 11.7'
DAM TOP WIDTH = 10'
WEIR COEFF. - DAM OVERFLOW = 3.0
WEIR EQUATION EXPONENT = 1.5
NOTE: LEVEL DAM CRGST - COMPUTER INPUT - INCLUDES
LENGTH ALLOWANCE FOR DIKE (SEE pg. D-6 & pg. D-7)

| DAM/DIKE LENGTH | ELEVATION |
|-----------------|-----------|
| 0 | 1395.8 |
| 176 | 1396.0 |
| 256 | 1396.5 |
| 322 | 1396.6 |
| 548 | 1397.1 |
| 846 | 1398.0 |


GEO-TECHNICAL SERVICES
Consulting Engineers & Geologists

SHEET NO. _____ OF _____
CALCULATED BY g/m DATE 4/8/
CHECKED BY _____ DATE _____
DAM PROFILE



GEO-TECHNICAL SERVICES
Consulting Engineers & Geologists


SHEET NO. _____ OF _____
CALCULATED BY SJM DATE 4/81
CHECKED BY _____ DATE _____
H & H



DIKE PROFILE


LOW LEVEL CREST DATA

| ELEVATION | LENGTH DIKE | LENGTH DAM | TOTAL DAM & DIKE |
|-----------|-------------|------------|------------------|
| 1395.8 | 0 | 0 | 0 |
| 1396.0 | 176 | 0 | 176 |
| 1396.5 | 256 | 0 | 256 |
| 1396.6 | 262 | 60 | 322 |
| 1397.1 | 290 | 258 | 548 |
| 1398.0 | 332 | 514 | 846 |



SPILLWAY PROFILE

EMERGENCY SPILLWAY



SPILLWAY RATING:

OUTLET SLOPE IS 0.8% ∴ CHECK NORMAL DEPTH FLOW IN
OUTLET CHANNEL AGAINST CRITICAL DEPTH NEAR
ENTRANCE TO SEE WHICH CONTROLS DISCHARGE

(n = normal depth c = critical)

$$Q_n = \frac{1.486}{n} A R^{2/3} \sqrt{S}$$

$$Q_c = \sqrt{\frac{g}{T}}$$


$$\text{POOL ELEV.} = y + \Delta h$$

$$\Delta h = (1 + C_i) \frac{V^2}{2g}$$

$$C_i = 0.3$$

* OPEN-CHANNEL HYDRAULICS
* BY VEN TE CHOW ON PAGE 311

OUTLET WORKS (as described by owner)



OUTLET RATING

6" INTAKE DISCHARGED 70 ± GPM ON DAY OF INSPECTION

MAIN OUTLET FLOW THRU 12" RISER & 10" PIPE. 4 CONDITIONS MAY
CONTROL FLOW - DEPENDING ON STAGE:

- COMPUTE ALL &
USE LOWEST
FOR RATING CURVE
1. WIER FLOW OVER RISER LIP - $Q_1 = 3TH^{1.5}$
 2. ORIFACE CONTROL - 12" RISER - $Q_2 = .62 \sqrt{2gH_2}$
 3. ORIFACE CONTROL - 10" OUTLET - $Q_3 = .62 \sqrt{2gH_3}$
 4. PRESSURE FLOW IN 10" OUTLET - $Q_4 = .62 \sqrt{2gH_4}$

BAYLY POND SPILLWAY RATING

| Y | Qn | Vn | En | Qc | Vc | Ec |
|------|------|------|--------|------|------|--------|
| 0.10 | 2 | 1.8 | 1395.6 | 1 | 1.0 | 1395.5 |
| 0.20 | 8 | 2.5 | 1395.7 | 5 | 1.6 | 1395.7 |
| 0.30 | 15 | 3.0 | 1395.9 | 10 | 2.0 | 1395.8 |
| 0.40 | 24 | 3.5 | 1396.0 | 17 | 2.4 | 1395.9 |
| 0.50 | 33 | 3.8 | 1396.2 | 24 | 2.8 | 1396.1 |
| 0.60 | 45 | 4.2 | 1396.3 | 33 | 3.1 | 1396.2 |
| 0.70 | 57 | 4.5 | 1396.5 | 44 | 3.4 | 1396.3 |
| 0.80 | 71 | 4.7 | 1396.7 | 55 | 3.7 | 1396.5 |
| 0.90 | 85 | 5.0 | 1396.8 | 68 | 4.0 | 1396.6 |
| 1.00 | 101 | 5.2 | 1397.0 | 82 | 4.2 | 1396.8 |
| 1.10 | 118 | 5.5 | 1397.1 | 97 | 4.5 | 1396.9 |
| 1.20 | 136 | 5.7 | 1397.2 | 113 | 4.7 | 1397.0 |
| 1.30 | 156 | 5.9 | 1397.4 | 130 | 4.9 | 1397.2 |
| 1.40 | 176 | 6.0 | 1397.5 | 149 | 5.1 | 1397.3 |
| 1.50 | 197 | 6.2 | 1397.7 | 169 | 5.3 | 1397.5 |
| 1.60 | 220 | 6.4 | 1397.8 | 190 | 5.5 | 1397.6 |
| 1.70 | 244 | 6.6 | 1398.0 | 212 | 5.7 | 1397.8 |
| 1.80 | 270 | 6.8 | 1398.0 | 237 | 5.9 | 1397.8 |
| 1.90 | 297 | 7.0 | 1398.1 | 263 | 6.2 | 1397.9 |
| 2.00 | 326 | 7.1 | 1398.1 | 291 | 6.4 | 1397.9 |
| 2.10 | 355 | 7.3 | 1398.2 | 319 | 6.6 | 1398.0 |
| 2.20 | 385 | 7.5 | 1398.2 | 349 | 6.8 | 1398.0 |
| 2.30 | 416 | 7.7 | 1398.3 | 380 | 7.0 | 1398.1 |
| 2.40 | 449 | 7.8 | 1398.3 | 413 | 7.2 | 1398.1 |
| 2.50 | 482 | 8.0 | 1398.4 | 446 | 7.4 | 1398.2 |
| 2.60 | 516 | 8.1 | 1398.4 | 481 | 7.6 | 1398.3 |
| 2.70 | 552 | 8.3 | 1398.5 | 517 | 7.7 | 1398.3 |
| 2.80 | 588 | 8.4 | 1398.5 | 554 | 7.9 | 1398.4 |
| 2.90 | 625 | 8.6 | 1398.6 | 592 | 8.1 | 1398.4 |
| 3.00 | 663 | 8.7 | 1398.6 | 631 | 8.3 | 1398.5 |
| 3.25 | 763 | 9.0 | 1398.7 | 735 | 8.7 | 1398.6 |
| 3.45 | 847 | 9.3 | 1398.8 | 823 | 9.0 | 1398.7 |
| 3.65 | 935 | 9.5 | 1398.9 | 917 | 9.3 | 1398.9 |
| 3.20 | 742 | 9.0 | 1398.7 | 714 | 8.6 | 1398.6 |
| 3.40 | 825 | 9.2 | 1398.8 | 801 | 8.9 | 1398.7 |
| 3.60 | 912 | 9.5 | 1398.9 | 893 | 9.3 | 1398.8 |
| 3.80 | 1003 | 9.7 | 1399.0 | 990 | 9.6 | 1398.9 |
| 4.00 | 1098 | 9.9 | 1399.1 | 1091 | 9.9 | 1399.1 |
| 4.20 | 1197 | 10.1 | 1399.2 | 1198 | 10.1 | 1399.2 |
| 4.40 | 1299 | 10.4 | 1399.3 | 1309 | 10.4 | 1399.3 |
| 4.60 | 1405 | 10.6 | 1399.4 | 1425 | 10.7 | 1399.4 |
| 4.80 | 1516 | 10.8 | 1399.4 | 1547 | 11.0 | 1399.5 |
| 5.00 | 1630 | 11.0 | 1399.5 | 1673 | 11.2 | 1399.7 |

```

5DEFFN1(Z)=INT(Z/.1+.5)*.1
10 FOR I=3.2 TO 6 STEP .2
20 Y=I: IF Y[1.8 THEN 30: Y=1.7
30 A=(16+3.45*Y)*Y: P=16+7.19*Y: T=16+6.9*Y
40 IF I[1.8 THEN 200
50 Y1=I-1.7: A=A+Y1*(2*T+Y1*3.7)/2
60 P=P+3.83*Y1: T=T+3.7*Y1
200 R=A/P
210 Q0=SQR(A*A*A*32.2/T): V0=Q0/A: E0=1395.4+Y+1.3*V0*V0/64.4
220 V1=4.75*R^(2/3): Q1=A*V1: E1=1395.4+Y+1.3*V1*V1/64.4
300 PRINT USING 500, I, FN1(Q0), FN1(V0), FN1(E0), FN1(Q1), FN1(V1), FN1(E1)
310 NEXT I
500Z #.# #.# #.# #.# #.# #.# #.# #.# #.#

```

BAYLY POND OUTLET RATING

| | Q ₁ | Q ₂ | Q ₃ | Q ₄ |
|--------|----------------|----------------|----------------|----------------|
| 1396.2 | 0.2 | 1.1 | 1.1 | 7.0 |
| 1396.3 | 0.2 | 1.1 | 1.1 | 7.1 |
| 1396.4 | 1.1 | 2.0 | 2.0 | 7.1 |
| 1396.5 | 2.0 | 3.0 | 3.0 | 7.1 |
| 1396.6 | 3.0 | 4.0 | 4.0 | 7.1 |
| 1396.7 | 4.0 | 5.0 | 5.0 | 7.1 |
| 1396.8 | 5.0 | 6.0 | 6.0 | 7.1 |
| 1396.9 | 6.0 | 7.0 | 7.0 | 7.1 |
| 1397.0 | 8.0 | 9.0 | 9.0 | 7.1 |
| 1397.1 | 10.0 | 11.0 | 11.0 | 7.1 |
| 1397.2 | 12.0 | 13.0 | 13.0 | 7.1 |
| 1397.3 | 13.0 | 14.0 | 14.0 | 7.1 |
| 1397.4 | 15.0 | 16.0 | 16.0 | 7.1 |
| 1397.5 | 17.0 | 18.0 | 18.0 | 7.1 |
| 1397.6 | 19.0 | 20.0 | 20.0 | 7.1 |
| 1397.7 | 22.0 | 23.0 | 23.0 | 7.1 |
| 1397.8 | 24.0 | 25.0 | 25.0 | 7.1 |
| 1397.9 | 26.0 | 27.0 | 27.0 | 7.1 |
| 1398.0 | 28.0 | 29.0 | 29.0 | 7.1 |
| 1398.1 | 31.0 | 32.0 | 32.0 | 7.1 |
| 1398.2 | 33.0 | 34.0 | 34.0 | 7.1 |
| 1398.3 | 35.0 | 36.0 | 36.0 | 7.1 |
| 1398.4 | 38.0 | 39.0 | 39.0 | 7.1 |
| 1398.5 | 41.0 | 42.0 | 42.0 | 7.1 |
| 1398.6 | 44.0 | 45.0 | 45.0 | 7.1 |
| 1398.7 | 46.0 | 47.0 | 47.0 | 7.1 |
| 1398.8 | 49.0 | 50.0 | 50.0 | 7.1 |
| 1398.9 | 51.0 | 52.0 | 52.0 | 7.1 |
| 1399.0 | 53.0 | 54.0 | 54.0 | 7.1 |
| 1399.1 | 56.0 | 57.0 | 57.0 | 7.1 |
| 1399.2 | 59.0 | 60.0 | 60.0 | 7.1 |
| 1399.3 | 61.0 | 62.0 | 62.0 | 7.1 |
| 1399.4 | 64.0 | 65.0 | 65.0 | 7.1 |
| 1399.5 | 67.0 | 68.0 | 68.0 | 7.1 |
| 1399.6 | 70.0 | 71.0 | 71.0 | 7.1 |
| 1399.7 | 73.0 | 74.0 | 74.0 | 7.1 |

```

10 FOR E=1396.2 TO 1399.7 STEP .1
20 H1=H2=E-1396.1
30 H3=E-1387:H4=E-1390
40 Q1=3*PI*H1*1.5:Q2=7.77*SQR(H2):Q3=2.6*SQR(H3):Q4=2.876*SQR(H4)
50 PRINT USING 100,E,Q1,Q2,Q3,Q4
60 NEXT E
100% ###.## ##.## ##.## ##.## ##.##

```

GEO-TECHNICAL SERVICES
Consulting Engineers & Geologists

CALCULATED BY *gfm*

DATE **4/81**


CHECKED BY

DATE

SPILLWAY RATING CURVE

HRC-1DB
RATING CURVE INPUT

| Elev. | Flow |
|--------|------|
| 1395.4 | 0 |
| 1395.5 | 1 |
| 1395.7 | 8 |
| 1396.0 | 24 |
| 1396.5 | 52 |
| 1397.0 | 106 |
| 1397.5 | 165 |
| 1398.0 | 285 |
| 1398.5 | 500 |
| 1399.0 | 1000 |
| 1399.5 | 1500 |



(OUTLET RATING CONT.)
T.W. estimated C 3'
OUTLET INV. = E.I. 1384.8
TOP OF 12" CHSE 1395.4 (ESTIMATED)

GEO-TECHNICAL SERVICES
Consulting Engineers & Geologists

SOIL TYPE _____

CALC. BY _____

CHECKED BY _____

SCALE _____

sfm

DATE

5/81

DATE

RESERVOIR STORAGE

| | <u>PLAN.</u> | <u>ACRES</u> |
|----------------------------------|--------------|--------------|
| SURFACE AREA (ASSUME EL. 1395.4) | 0014 | 13 |
| EL. 1400 (CONTOUR) | 0018 | 16.5 |

STORAGE UNKNOWN

ASSUME STORAGE = 0 @ EL. 1385

$$\text{STORAGE AT } 1395.4 = \frac{10.4}{3} (13) = 45 \text{ Ac-ft.}$$

$$\begin{aligned} \text{STORAGE AT } 1400.0 &= 45 + \frac{4.6}{3} (16.5 + 13 + \sqrt{13(16.5)}) \\ &= 113 \text{ Ac-ft} \end{aligned}$$

INTERPOLATED STORAGE AT MAX. POOL

at EL. 1395.8

$$\text{STORAGE} = 51 \text{ Ac-ft}$$

| ELEV. | AREA (Ac) |
|--------|------------------------|
| 1385.0 | 0 (NATURAL STREAM BED) |
| 1395.4 | 13 (NORMAL W.S. ELEV.) |
| 1400.0 | 16.5 (CONTOUR) |

GEO-TECHNICAL SERVICES
Consulting Engineers & Geologists

JOB BAYLY ROAD

SHEET NO

OF

CALCULATED BY SPM

DATE

5/81

CHECKED BY

DATE

SCALE

DETERMINE 100 YR FLOOD

REF. 1) "REGIONAL FREQUENCY STUDY, UPPER DELAWARE AND HUDSON RIVER BASINS" NEW YORK DIST. C.O.E. 1974

2) C.O.E. MEMO 4/22/81

$$\log Q_m = C_m + 0.87 \log A$$

$$A = 0.12 \text{ mi}^2$$

$$C_m = 1.8$$

$$\log Q_m = 1.8 + 0.87 \log(.12) = 1.0$$

$$S = C_s - 0.05 \log(A)$$

$$C_s = 0.37$$

$$S = 0.37 - 0.05 \log(.12) = 0.416$$

$$\log Q_p = \log Q_m + K_{p,g} S$$

$$p = 100 \text{ yr.}$$

$$g = .5$$

$$K_{p,g} = 2.70$$

$$\log Q_{100} = 1 + 2.7(.416) = 2.12$$

$$Q_{100} = 132.8 \text{ say } \underline{\underline{130 \text{ cfs}}}$$

$$\text{SPILLWAY CAPACITY AT EL. 1395.8} = 13 \text{ cfs}$$

100 yr. flood will overtop the dike

zhu

5/91

ESTIMATE EFFECT OF A FAILURE OF BAYLY DAM ON
THE DOWNSTREAM QUARNO DAM.

QUARNO DAM NDI ID PA 00416


INSPECTION BY BERGER ASSOC. 1981

HIGH HAZARD DAM

PR. AREA = 0.43 mi²

DATA FROM BERGER REPORT

| | Elev. | Disch. | STORAGE |
|---------------|--------|---------|--------------------|
| NORMAL POOL | 1316.0 | - | 6 ac-ft |
| EMERG. SPWY | 1320.5 | 40 cfs | (168) interpolated |
| TOP DAM | 1324.7 | 861 cfs | 259 ac-ft |
| 1/2 PMF STAGE | 1322.5 | | (206) |
| 1.0 PMF STAGE | 1324.4 | | (252) |



REMARK NO 1 - If Bayly dam were to fail the failure would be at the dike which is 1' lower than the dam itself. THE BOTTOM OF THE BREAK WOULD BE EL. 1391 AND THE RELEASE VOLUME WOULD BE 36 Ac-ft*

* 51 (MAX POOL) - 15 (STORAGE AT EL. 1391)

PREMISE No. 2 - As Quarno Dam has 91 ac-ft storage available above the emergency spillway crest, a dam break analysis of Bayly when routed through Quarno would not overtop Quarno if it were conducted as per the C.O.E. guidelines ... is no additional inflow from the downstream drainage area.


Note that sufficient storage (53 ac-ft) is available if the Quarno Dam is at the $\frac{1}{2}$ PMF peak stage also.

PREMISE No. 3 - Overtopping of Quarno Dam by a breach of Bayly could only occur if the time of breach coincides with the peak inflow to Quarno from the drainage area outside of Bayly's. And would only occur for flows near the full PMF.

CONCLUSION - A breach of Bayly dam would not cause overtopping of Quarno Dam
AND the "significant Hazard Classification for Bayly is appropriate

APPENDIX E

EXHIBITS



APPENDIX F

GEOLOGY

BAYLY POND DAM

APPENDIX F

GEOLOGY

Bayly Pond Dam and reservoir area are located within the Glaciated Allegheny Plateau Section of the Appalachian Plateaus Physiographic Province. Deposits of glacial drift of variable thickness cover the entire area. The drift was deposited by the Wisconsin Ice Sheet during the Pleistocene period of geologic time.

The glacial drift is composed primarily of till which is a reddish brown, unsorted compact mixture of clay, silt, sand, gravel, and cobbles with occasional boulder sized pieces. The stone pieces are sub-angular to rounded and consist mainly of sandstone and siltstone derived from the Catskill formation, the dominant rock formation in the area. The clay content and compact nature of the till makes it a relatively impervious soil type.

Some deposits of glacial outwash are also found in the area. The outwash is composed of loose, poorly sorted to stratified deposits of silt, sand, and gravel. The outwash deposits are generally very pervious.

Other loose pervious soils in the area are the recent deposits of alluvial silt, sand, and gravel with some clay. These soils are localized and limited to streambeds and flood plain areas.

The bedrock underlying the entire dam and reservoir area is the Catskill Formation of the Susquehanna Group. This group of formations is of Upper Devonian age. The Catskill Strata generally consists of well-indurated red shale, siltstone, and fine sandstone with some gray, green, and brown shale, siltstone, and sandstone layers. Occasional conglomeratic layers are encountered. The red shales are the dominant lithology and the residual soils derived from this rock are usually high in clay and silt and contain numerous flaky and angular fragments and flat, slabby boulders. The area between the main dam and the dike is covered with many such flat, slabby boulders.

The regional structure of the bedrock in the area indicates that the bedrock underlying the dam and reservoir area is near-horizontal. The regional strike of the strata is northeast-southwest.

Although depth to the bedrock at the dam site is unknown, the steep excavated earth channel below the road culvert downstream of the dam indicates at least 6 feet of overburden soil in the area.

*Ref.: Ground Water of Northeastern Pennsylvania, Stanley W. Lahman
1937, Bulletin W-4, Pennsylvania Geologic Survey.*

